

THE MAHARASHTRA STATE CO-OP. BANK LTD., MUMBAI
(Incorporating the Vidarbha Co-op. Bank Ltd.)

**Sir Vithaldas Thackersey Smruti Bhavan,
9, Maharashtra Chamber of Commerce Lane,
Fort, Mumbai - 400 001.**

TENDER NOTICE

Sealed quotations are invited from experienced contractors for the repair and allied works at Sector 19 B Turbhe Extension Counter, Vashi Branch , Navi Mumbai.

Interested contractors requested to submit the quotation in the following format on or before 23-06-2022 during the office hours i.e. 10:15 a.m. to 5:15 p.m. In the and at the address given below :

Sr.No.	Particulars	Unit	Approx Qty	Rates Labour + Material	Amt.Rs.
1	Plaster Breaking work Breaking & Removing existing damaged concrete / plaster of RCC columns, beams and walls etc. by carefully removing only the loose & disinfected plaster of any thickness & carting away debris (to approved dumping ground) to all leads & lifts.	sq.ft	175.00	--	
2	Concrete Repair using Forsook ready made repair Mortar Providing and applying single component fibre reinforced thixotropic repair mortar of forsook (Renderoc SP40) up to 50 mm thickness in 20 mm layers for repairs to the affected portions of columns, beams and ceiling as per following Steps as per EIC	sq.ft.	45.00	--	
a)	Remove rust from exposed reinforcement by wire brushing, mechanical brushing & applying two coats of Rust Remover chemical	--	--		
b)	Application of two coats of REINFORCEMENT PROTECTIVE CHEMICAL by brush to prevent further rusting of steels & sprinkling dry sand on the reinforcement.	--	--		
c)	Application of BONDING CHEMICAL + Cement slurry in (1:1) as primer cum bonding coat on old concrete.	--	--		
d)	Use Render SP40 Ready to use mortar	--	--		
f)	Keep surface rough to receive plaster	--	--		

3	Internal Plaster Providing & applying cement plaster in single coat in avg. thk. of 20 mm in q:4) curing for 3 to 4 days as per EIC	sq.ft.	175.00		
4	POP fall ceiling Providing and fixing Patchwork fall ceiling as per EIC	sq.ft.	100.00		
5	Internal Painting by Asian Plastic Paint Providing and applying two coats of Plastic paint including surface preparation as per EIC	sq.ft.	475.00		
6	Synthetic Enamel Paint Providing & applying one coat of Red oxide and two coats of Enamel paint on shutter door as per EIC	sq.ft.	100.00		
7	Wall Tiles Providing and fixing 12" x 18" wall tiles in line level Jonhson or equivalent as per EIC	sq.ft.	130.00		
8	Providing and fixing Aluminum Frame Bakelite Panel Door for toilets including all necessary Fittings and fixture etc. complete size 2'3" x 6'6" as per EIC.	Nos.	3.00		
9	Providing and fixing heavy type rolling shutter in MS with all necessary fittings and fixtures with base coat of reel oxide and 2 coats of approved shade enamel paint, with Godrej Navatal lock complete as per EIC.	sq.ft.	85.00		
10	Providing and fixing Green Marble frame to 2'3" x 6'6" door size as per EIC.	RFT	50.00		
	Total				

Stamp & Signature of Contractor :

Phone No.

Terms & Conditions :

- 1) Tender forms to be issued from 17-06-2022 to 23-06-2022 during office hours i.e. 10:15 a.m. to 5:15 p.m. (Expect Bank Holidays)
- 2) Tender to be collected from the address given below or if downloaded from website D.D. of Rs.500/- plus GST amount in the name of the Maharashtra State Coop.Bank Ltd., should be enclosed with Tender Form
- 3) Price Bid documents shall be filled in correctly no terms and conditions on part of the contractor shall be entertained.
- 4) Incomplete or overwritten Tender shall be rejected.
- 5) Tenders for Repair and allied work at Turbhe, Extension Counter, Vashi Branch, should be subscribed on the envelope.

- 6) The Bank reserves the right to accept or reject any or all Tenders without assigning any reason for doing so.
- 7) Tender forms shall be submitted on or before 23-06-2022 upto 5.15 p.m. at the following address.
- 8) No advance will be paid.
- 9) Any mishap or accident will be the responsibility of contractor.
- 10) Tender should be accomplished with labour act.
- 11) Time period of work is 30 days from issuing work order.
- 12) Payment will be made as actual measurement.
- 13) The earnest money deposit amounting to Rs.2,000/- as demand draft or pay order of Nationalized or Sheduled Bank in drawn in favour of The MSC Bank Ltd., payment at Mumbai.
- 14) Defect liability period shall be of Twelve months from the date of completion as certified by the EIC.
- 15) Tender and material of the contractor will be under his control & Bank will not be responsible for the same in any manner. The contractor should follow all safety rules and norms applicable to this work.
- 16) Contractor has to arrange all tool trackles etc.
- 17) Before participating in the Tender site visit is compulsory, otherwise tender will be rejected.
- 18) Any damages which carrying out the said work will be the responsibility of the contractor.
- 19) Tender to be submitted at

Address :

The Manager

(General Administration)

The Maharashtra State Co-op.Bank Ltd.,

3rd floor, Head Office,

Sir Vithaldas Thackersey Smruti Bhavan,

9, Maharashtra Chamber of Commerce Lane,

Fort, Mumbai- 400 001.

Phone No. 022 - **69801162 / 69801167**